BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work:- Re-Construction of at Drains at 1st Main Road Kirloskar layout in Ward No 14 Bagalagunte

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	**76.68**	90.72	**Rupees Ninty & Seventy two Paise Only**
2	Removing B.S.Slab of drain and stacking etc., complete	Sqm	**230.04**	50.11	Rupees Fifty & Eleven Paise only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	**70.29**	4290.84	Rupees Four Thousand two hundred ninty & Eighty four paise only
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	**33.02**	4779.00	Rupees Fortythousand seven hundred Seventy nine Only
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	Sqm	230.04	70.04	Rupees Seventy & Four Paise Only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick	Sqm	153.36	343.44	Rupees Three hundred forty three & Forty four Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-2
KRIDL, BBMP DIVISION
BANGALORE - 560 010

Executive Engineer

7	Providing and constructing precast **concrete solid blocks** with compressive strength not les than 35 g/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size **40x20x20** cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	**340.80**	924.48	Rupeed Nine hundred twenty four & Forth eight Paise only
8	Providing & fixing pre cast **solid concrete Kerb** stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete of size 450x20x400 mm	No	946.67	316.44	Rupees Three hundred sixteen & Forty four Paise Only
9	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	**383.40**	1600.00	Rupees OneThousand Six Hundred Only
10	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	85.50	78.24	Rupees Seventy Eight & Twenty four Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP DIVISION
BANGALORE - 560 010

Executive engineer